#### London





Wood Wharf Ansicht

© CanaryWharfGroup, Wood Wharf SE Aerial preview 2014, CC BY-SA 4.0

MAX FRANK supplied Stremaform® concrete jointing system to Canary Wharf's new district. The use of Stremaform® enabled significant time and cost advantages to be achieved on-site.

Extending to 23 acres, the Wood Wharf project represents one of central London's largest privately owned development sites and is recognised as being of major importance on a local, national and international level.

Project Architects include; Allies and Morrison, Darling Associates, KPF, Herzog & de Meuron, Stanton Williams Architects, Grid Architects, and Patel Taylor.

Canary Wharf's new district, Wood Wharf, has been designed by Allies and Morrison Architects and they have created a strong and complementary design, providing; mixed-use development, commercial offices, retail space, housing and inter-connected public space.

The 1st phase includes Plot G3, constructed by O'Halloran & O'Brien, where MAX FRANK supplied Stremaform®.

Stremaform® is a proven concrete to concrete jointing system which enables the Contractor to pour a sequence of concrete pours, whilst attaining an established concrete bond throughout the joint - ultimately reducing the construction period.

# The "self-supporting" solution comprised the following components:

■ Stremaform® Strong - Stremaform® mesh with girder

## Type of building:

### **Clients and Developers:**

Canary Wharf Group, <a href="https://group.canarywharf.com/">https://group.canarywharf.com/</a>

#### Architect:

Allies and Morrison Architects, <a href="http://www.alliesandmorrison.com/">http://www.alliesandmorrison.com/</a>

#### **Building contractor:**

O'Halloran & O'Brien Ltd, <a href="http://www.ohob.com/">http://www.ohob.com/</a>

## **Completion:**

2023

#### **Project link:**

https://group.canarywharf.com/portfo lio/wood-wharf/

Wood Wharf Creation date: 20.04.2024

## London



stiffening

- Stremafix® Anchors to increase concrete pour rates
- Stremaform® Spacers offer a technical solution to capture grout during the concrete pour

Erika Simionescu (O'Halloran & O'Brien Ltd) provided all of the necessary structural information relating to the proposed 2m deep stop-end and pour sequence for the Building G3 basement slab. The slab construction had the added complexity of heavy, congested reinforcement with numerous layers in a confined working space. MAX FRANK's design team assessed all of the supplied joint information and determined that the "Stremaform® Strong" system with Stremafix ® anchors was required. Stremaform® enabled O'Halloran & O'Brien to achieve a proven concrete bond to the next concrete pour - an easy installation in a technically tricky working environment - and was able to withstand pour pressures of 38kN/m2 without the need of any additional propping.

Maksymilian Jarusewicz (O'Halloran & O'Brien Ltd) and his team, commented that the Stremaform® proved to be 6 times faster to install than other systems on the market and it was a solution that the O'Halloran & O'Brien team would definitely use again on future projects.

The tailor-made Stremaform® system was delivered to site in less than 2 weeks from order.

The construction of any concrete joint is simplified by using Stremaform® self-supporting permanent jointing system – the process is thus accelerated allowing significant time and cost advantages to be achieved on-site.

## London



## **Products used:**





Wood Wharf preview © CanaryWharfGroup, Wood Wharf SE Aerial preview 2014, CC BY-SA 4.0



Wood Wharf, London, E14 © Allies and Morrison Architects



Wood Wharf, London, E14 © Allies and Morrison Architects (Architect's Impression)

## London





Stremafix® Anchors © www.maxfrank.com



Stremaform® Day Joint Solution © www.maxfrank.com