

# Wood Wharf

London



Wood Wharf Ansicht

© CanaryWharfGroup, Wood Wharf SE Aerial preview 2014, CC BY-SA 4.0

**MAX FRANK supplied Stremaform® concrete jointing system to Canary Wharf's new district. The use of Stremaform® enabled significant time and cost advantages to be achieved on-site.**

Extending to 23 acres, the Wood Wharf project represents one of central London's largest privately owned development sites and is recognised as being of major importance on a local, national and international level.

Project Architects include; Allies and Morrison, Darling Associates, KPF, Herzog & de Meuron, Stanton Williams Architects, Grid Architects, and Patel Taylor.

Canary Wharf's new district, Wood Wharf, has been designed by Allies and Morrison Architects and they have created a strong and complementary design, providing; mixed-use development, commercial offices, retail space, housing and inter-connected public space.

The 1st phase includes Plot G3, constructed by O'Halloran & O'Brien, where MAX FRANK supplied Stremaform®.

Stremaform® is a proven concrete to concrete jointing system which enables the Contractor to pour a sequence of concrete pours, whilst attaining an established concrete bond throughout the joint - ultimately reducing the construction period.

**The "self-supporting" solution comprised the following components:**

- **Stremaform® Strong** - Stremaform® mesh with girder

## Type of building:

### Clients and Developers:

Canary Wharf Group,  
<https://group.canarywharf.com/>

### Architect:

Allies and Morrison Architects,  
<http://www.alliesandmorrison.com/>

### Building contractor:

O'Halloran & O'Brien Ltd,  
<http://www.ohob.com/>

### Completion:

2023

### Project link:

<https://group.canarywharf.com/portfolio/wood-wharf/>

# Wood Wharf

London



stiffening

- **Stremafix® Anchors** - to increase concrete pour rates
- **Stremaform® Spacers** - offer a technical solution to capture grout during the concrete pour

Erika Simionescu (O'Halloran & O'Brien Ltd) provided all of the necessary structural information relating to the proposed 2m deep stop-end and pour sequence for the Building G3 basement slab. The slab construction had the added complexity of heavy, congested reinforcement with numerous layers in a confined working space. MAX FRANK's design team assessed all of the supplied joint information and determined that the "Stremaform® Strong" system with Stremafix® anchors was required. Stremaform® enabled O'Halloran & O'Brien to achieve a proven concrete bond to the next concrete pour - an easy installation in a technically tricky working environment - and was able to withstand pour pressures of 38kN/m<sup>2</sup> without the need of any additional propping.

Maksymilian Jarusewicz (O'Halloran & O'Brien Ltd) and his team, commented that the Stremaform® proved to be 6 times faster to install than other systems on the market and it was a solution that the O'Halloran & O'Brien team would definitely use again on future projects.

The tailor-made Stremaform® system was delivered to site in less than 2 weeks from order.

The construction of any concrete joint is simplified by using Stremaform® self-supporting permanent jointing system - the process is thus accelerated allowing significant time and cost advantages to be achieved on-site.

# Wood Wharf

London

## Products used:



Stay-in-place formwork for  
working joints Stremaform®



Stay-in-place formwork for  
working joints Stremaform®



Wood Wharf preview

© CanaryWharfGroup, Wood Wharf SE Aerial preview 2014, CC BY-SA 4.0



Wood Wharf, London, E14

© Allies and Morrison Architects (Architect's Impression)



Wood Wharf, London, E14

© Allies and Morrison Architects



# Wood Wharf

London



Stremafix® Anchors  
© [www.maxfrank.com](http://www.maxfrank.com)



Stremaform® Day Joint Solution  
© [www.maxfrank.com](http://www.maxfrank.com)